

General Specification for Civil Engineering Works**2006 Edition****AMENDMENT NO. 2/2017****VOLUME 1****SECTION 1 GENERAL****WORK ON ROADS**

- (a) Clause 1.14 (1) **Add the following after** “temporary traffic arrangements shall be in accordance with conditions and restrictions imposed by the Commissioner for Transport and the Commissioner of Police.” :

In case works with temporary traffic arrangement affecting carriageway, including that with pedestrian diversion onto carriageway, the details of the temporary traffic arrangements, including necessary supporting material such as staging of works, traffic impact assessment, drawings, plans and calculations shall be prepared and submitted by the Contractor. These details shall be prepared and signed by a professional engineer who has been a corporate member of the Hong Kong Institution of Engineers in the Civil Discipline or Logistics and Transportation Discipline (or has possessed equivalent qualifications) for at least 3 years.

SECTION 10 CONCRETE CARRIAGEWAYS**TRIALS**

- (b) Clause 10.22 **Replace each of the six slump values and the average of the six slump values with “85” and “80” respectively.**

VOLUME 2**SECTION 21 MARINE WORKS****APPENDIX 21.2 - SPECIFICATION FOR REINFORCED CONCRETE IN MARINE ENVIRONMENT (TO BE READ IN CONJUNCTION WITH SECTION 16 AND THE AMENDMENTS)**

- (c) Clause 21.2.3 (3) **Replace the sub-clause with the following:**

(3) The chloride content of admixtures shall not exceed 0.1% by mass of the admixture in accordance with BS EN 934-1.

**Quality Management & Standards Unit
Civil Engineering and Development Department
21 December 2017**