# **General Specification for Civil Engineering Works**

#### 2020 Edition

# **AMENDMENT NO. 3/2025**

# **VOLUME 1**

### **SECTION 6** EARTHWORKS

#### COMPACTION OF FILL MATERIAL

- (a) Clause 6.48 Add "The moisture content of the fill material shall be adjusted by wetting or drying on site to achieve the required relative compaction." at the end of item (3).
- (b) Clause 6.49 Clause 6.49 is not used.

#### **TESTING: FILL MATERIAL - MOISTURE CONTENT**

- (c) Clause 6.77 Clause 6.77 is not used.
- (d) Clause 6.78 Item (1) of Clause 6.78 is not used.

Replace "method of testing" with "moisture content" and add "tested" after "shall be" in item 2.

- (e) Clause 6.79 **Clause 6.79 is not used.**
- (f) Clause 6.80 Clause 6.80 is not used.
- (g) Table 6.5 **Delete** "samples to be tested for moisture content and number of" **from the table description.**

Delete "No. of samples" from the table.

## **SECTION 7 GEOTECHNICAL WORKS**

### **SOIL-CEMENT FILL**

(h) Clause 7.116 **Delete** "Soil-cement fill shall be at optimum moisture content during compaction. The tolerance on the optimum moisture content percentage shall be  $\pm 3$ ." **in item (2).** 

Technical Secretariat Unit Civil Engineering and Development Department 26 August 2025